



भाकृअनुप-राष्ट्रीय केला अनुसंधान केंद्र
(भारतीय कृषि अनुसंधान परिषद)
तोगमलै रोड थायनूर पोस्ट.
तिरुचिरापल्लि. -६२० ९०२. तमिलनाडु

ICAR - National Research Centre for Banana
(Indian Council of Agricultural Research)
Thogamaiai Road, Thayanur P.O.
Tiruchirapalli - 620 102, Tamil Nadu, India



F.No.9-4(55)/2016-Estt.

4396

Date: 08.11.2016

EXTENSION OF DATE

Sub : **Extension of Date for receipt of Quotations** for Repair of Transgenic Glass Houses at the ICAR – NRCB, Trichy – Reg.

Ref : This Office quotation inviting notice of even no. dated 19.10.2016

The last date for receipt of Quotations for “Repair of Transgenic Glass House” at the ICAR – NRCB, Trichy is **EXTENDED upto 3.00PM on 23.11.2016**. All other terms and conditions remain unchanged.

Senior Administrative Officer

Copy to:

1. The Chairman (WLM)
2. The Chairman-PMEC for uploading in NRCB website
3. Member Secretary (WLM)
4. The Nodal Officer- CPPP for uploading in CPP Portal
5. PS to Director

Pl. upload in NRCB website

J. Prasad
10/11/16

**ICAR – NRC for Banana
Trichy – 620 102**

Details of work

ii) Glass House repair

Sl.no	Description	Quantity	Rate. Rs	Amount Rs.
1	<p>Providing and fixing of Cooling pad size of thickness-4" (100mm) with UPVC enclosure (for rust free structure) for box type fixing arrangement for cooling pad with water inlet pipe 1" size (25mm) and water outlet pipe 4"size (100mm) upto ground water storage tank (all in UPVC materials)</p> <p>Completing the work, including fixing of cooling pads in a UPVC enclose arrangement, with valve arrangement, extra collecting arrangement for spill over water from cooling pad during running</p> <p>All inlet and outlet water supply arrangements from sump -cooling pad –again to sump</p> <p>6.3m x 2.1 m – 2 nos.</p>	28 sq.m		
2	Providing and fixing of 1-HP motor with suction and delivery pipeline arrangement from tank to cooling pad including the electrical power supply, wiring work and all materials	2 nos.		
3	Providing and fixing of Temperature controller with sensor unit, wiring to temperature controller unit with any other required materials to complete the work	2 nos		
4	Providing and fixing of single phase, axial slow speed exhaust fan with motor, wiring work to motor and connected to temperature controller and cooling pad pump , cutting of existing poly carbonate sheet and making of frame ,all work to complete	2 nos		
5	Supplying of Single phase, axial slow speed exhaust fan with motor, for spare purpose	1 no		
6	Providing of 1-HP mono block motor for spare.	1 no		
Total				